

When you
think with a
global mind
problems
get smaller

Control of groundwater to excavations: Barriers and dewatering

Presented to IAH – NSW Branch
June 2018



Control of groundwater to excavations

Content

Purpose

Control Methods

Assessment Tools

- Empirical

- Analytical

- Semi-analytical

- Numerical

Examples

References

01 Purpose

Control of groundwater to excavations

Purpose

Why control groundwater to excavations?

Design

- Make inflows/levels more predictable

Construction

- Make the site more manageable
- Reduce treatment volume
- Reduce impacts

Operation

- Reduce on-going cost of pumping/treatment
- Comply with regulatory requirements
- Reduce impacts
- Reduce risk from contamination

Typical introduction to groundwater dewatering



02

Control methods

Control of groundwater to excavations

Control methods - Barriers

Diaphragm Wall

- Panel construction under bentonite, full reo cage
- Excellent control, Seepage: anchor penetrations & base

Secant pile

- Overlapping piles (hard/soft), reo cage in half piles
- Good control, Limited depth – gaps from splay

Cutter Soil Mix

- Installed in panels like D Wall, soil mixed with cement
- Reinforcement limited to I beams

Jet grout

- Spinning jet cuts and mixed soil with grout
- Can provide good control – typically temporary
- Can be used with secant pile/contiguous piles



Control of groundwater to excavations

Control methods - Barriers

Soil mix wall

- Soil mixed with bentonite in trench
- Low permeability, non structural
- Control of groundwater flow only

Sheet pile walls

- Interlocking steel sheets
- Typically temporary, sheets reusable
- Vibration during installation can be problematic



Control of groundwater to excavations

Control methods – Recharge / Extraction


Recharge wells and trenches

- Recharge of clean water to prevent adverse impacts
- Harder to get water into the ground



Extraction wells – capture contaminated water

- Pumping downgradient to capture contaminated groundwater
- Need to assess existing gradient and flow rate
- Extract at a rate equal to width time the flow rate



03 Tools


Control of groundwater to excavations - Tools

Making predictions

Analysis methods

- Empirical
- Analytical
- Semi-analytical
- Numerical

Finite element / finite difference / boundary element




Control of groundwater to excavations - Tools

Making predictions

Illustrative section – things of interest


- Flow (q)
- Drawdown (h)



Control of groundwater to excavations - Tools

Making predictions – Flow beneath wall


Flow beneath cut off wall



Control of groundwater to excavations - Tools


Making predictions

Flow beneath a wall (Harr 1962 after Polubarinova-Kochina 1952)



Drawdown $h = 12$ m
Penetration $s = 2$ m
Rock permeability $k = 0.01$ m/d
Rock thickness $T = 16$ m
 $s/T = 0.125 \rightarrow q/kh = 0.95$


$$q = 0.95 \times 0.01 \text{ m/d} \times 12 \text{ m} = 0.114 \text{ m}^3/\text{d/m}$$




Control of groundwater to excavations - Tools

Flow beneath cut off wall

Further useful result







$$\tan \pi \epsilon = \sqrt{\frac{k_2}{k_1}}$$



Control of groundwater to excavations - Tools

Flow beneath cut off wall


Further useful result – excavation of limited width (trenches) - Harr 1962



Control of groundwater to excavations - Tools

Making predictions


Extent of drawdown – Extensive aquifer



Control of groundwater to excavations - Tools


Making predictions

Extent of drawdown – Extensive aquifer (delayed yield –
Kruseman and de Ridder (1991) (after Neuman)




Control of groundwater to excavations - Tools

Making predictions



Transmissivity T (m ² /d)	50	50	50	50
Storativity S	0.00001	0.00001	0.00001	0.00001
Aquitard thickness B (m)	4	4	4	4
Aquitard permeability k_v (m/d)	0.0000001	0.002	0.002	0.002
Upper unit specific yield	100	100	100	0.05
Pumping rate (m ³ /d)	86.4	86.4	86.4	86.4
Time (d)	180	180	180000	180
	Theis	Hantush	Hantush	Boulton


Hunt (2012)
provides
spreadsheet
tools



Control of groundwater to excavations - Tools

Making predictions

Drawdown extent – recharge balances extraction



$$h(r) = \sqrt{h_e^2 + \frac{n}{k} \left(R^2 \ln \left(\frac{r}{R_e} \right) - \frac{(r^2 - R_e^2)}{2} \right)}$$

$$Q = \pi n (R^2 - R_e^2)$$


Control of groundwater to excavations - Tools

Recharge design

Example – Cut off wall

Trapezoidal shape (about 60 m x 60 m)

Permeable horizon underlain by rock




Control of groundwater to excavations - Tools

Recharge design

Example – Cut off wall

Step 1 – Calculate seepage below wall

Step 2 – Integrate aquifer solution per wall



Control of groundwater to excavations - Tools


Recharge design

Example – Cut off wall

Step 1 – Calculate seepage below wall

Step 2 – Integrate aquifer solution per wall

Step 3 – Combine for all walls



Control of groundwater to excavations - Tools

Recharge design

Example – Cut off wall

Step 1 – Calculate seepage below wall

Step 2 – Integrate aquifer solution per wall


Step 3 – Combine for all walls

Step 4 – Include recharge wells

Excel spreadsheet contains the results

Alternate layouts can be tested

Note with recharge the effects are localised and the nature of the aquifer more widely does not affect the outcome.



Control of groundwater to excavations - Tools


Numerical methods

Use where analytical methods are too crude

Complex profiles

Free surface problems (drained walls)

Regional impacts



04

Examples

Northside storage tunnel – grouting control

Tempe – soil mix wall

Barangaroo Stage 1A – diaphragm wall



NST Background

Sydney Water Project - Collects four main sewer overflows

15.8km from Lane Cove River to North Head STW


Tunnel invert RL-43m to RL-96.5m

Northern branch tunnel 3.7km long to Scotts Ck. Tunnelling by four TBMs (3.8m to 6.6m dia.)

Tunnel unlined

Project completed before the 2000 Olympics

NST – Long Section




Long section of main tunnel


Northside storage tunnel - Middle Harbour - Clontarf



Middle Harbour Long Section



NS 35-OB1 Drawdown - Trial



Grouting at Clontarf

Probe ahead grouting

Annular patterns of up to 56 holes


Grout take 3.75kg/uL/m

180t cement


Advance slowed from 225m/week to 5m/week (one month for worst 25m)

Inflow limited to 18L/s

Permeability controlled to 1uL



Northside Storage Tunnel – Clontarf



Control of groundwater to excavations

Northside Storage Tunnel


- No numerical modelling – evaluation carried out by direct extrapolation from measurement and simple hand calculation
- Demonstrated construction without grouting control would result in very high inflow (> 100 L/s) and cause settlement of piled syphon
- Grouting proved effective though time consuming
- Early warning allowed rescheduling of other operations to avoid delay to overall program
- Ground – tightened up with time
- Monitoring proved a useful tool to evaluate performance during construction and during operation

Control of groundwater to excavations

Tempe landfill remediation

Tempe Landfill

- Operated from early 1900's
- Up to 17 m fill underlain by alluvial/residual soils and sandstone
- Leachate entering Alexandria Canal
- 1.6 km soil/bentonite wall and drain
- Used long reach excavator (20 m)





Control of groundwater to excavations

Tempe landfill barrier

Soil mix wall

- Wall performance tested by closed cell – not conclusive
- Alexandria Canal tidal
- During construction monitoring assess performance
- Series of wells either side of alignment
- Monitoring demonstrated stopping of tidal response and raised groundwater level



Control of groundwater to excavations Barangaroo Stage 1A




Control of groundwater to excavations Barangaroo Stage 1A



Control of groundwater to excavations

Barangaroo Stage 1A – Ground conditions

- Site contained deep fill (highly transmissive) over alluvium and a sloping rock profile
- Rock profile contained buried cliff lines
- Diaphragm wall constructed to allow excavation 8 m below sea level
- Wall needed to reach rock at depth of up to 30 m
- Tanked structure with tie down piles a thick base slab connected to the diaphragm wall



Control of groundwater to excavations


Barangaroo Stage 1A – Ground conditions



Control of groundwater to excavations

Barangaroo Stage 1A – Ground conditions


- Constructed by Menard Bachy
- 700 m long diaphragm wall (6 m x 1 m panels) up to about 30 m deep performed very well
- Anchors installed above sea level to reduce seepage
- Construction inflows less than 3 L/s (beneath the wall)



Control of groundwater to excavations

Barangaroo Stage 1A – Ground conditions

- Monitoring of piezometers during wall construction
- Full tidal response 40 m back from the water of Darling Harbour
- Tidal response inside the wall dropped dramatically as D wall panels near monitoring bores were completed



05 Closing

Control of groundwater to excavations

Closing

Comments

- Various proven groundwater control methods available
- Barrier methods are mature
- Assessment methods revolve around flow estimation and assessment of impact
 - Best to extrapolate for local experience
 - Analytical methods quite satisfactory
 - Semi-analytical methods can address more complex situations
 - Numerical methods
- Examples
 - Monitoring valuable to evaluate performance

Paraphrasing the great John Booker

Use simple hand calculations where possible

If necessary use analytical or semi-analytical methods

If desperate use numerical methods



John Robert Booker 1942-1998

06

References

Control of groundwater to excavations

References

- Boulton, N.S. (1963) Analysis of data from non-equilibrium pumping tests allowing for delayed yield from storage. *Proc. Inst. Civil Eng.*, **26**, Paper No. 6693: 469-482.
- Edelman, J.H. (1972) Groundwater Hydraulics of Extensive Aquifers, International Institute of Land Reclamation and Improvement, Wageningen, The Netherlands.
- Hantush, M.S. (1967) Flow to wells in aquifers separated by a semipervious layer. *Journal of Geophysical Research*, 72(6), 1709-1720.
- Harr, M.E. (1962) Groundwater and seepage, McGraw-Hill.
- Huisman, L. (1972) Groundwater recovery, Macmillan.
- Hunt, B. (2012) Groundwater analysis using Function.xls, Civil Engineering Department, University of Canterbury.
- Kruseman, G.P. and N.A. DeRidder 1979. *Analysis and evaluation of pumping test data*. International Institute for Land Reclamation and Improvement, Wageningen , The Netherlands.
- Polubarinova-Kochina (1952) Theory of groundwater motion. Gostakhizdat, Moscow, 1952.
- Theis, C.V. (1935) The relation between the lowering of the piezometric surface and the rate and duration of discharge of a well using ground-water storage. *Trans. Am. Geophys. Union*, 16: 519-524.
- Verruijt, A. (1970) Theory of groundwater flow, Mcmillan.